



**CITY OF Sterling Heights**

InnovatingLiving

Richard J. Notte Sterling Heights City Center

City Hall

40555 Utica Rd. | P.O. Box 8009  
Sterling Heights, MI | 48311-8009

TEL 586.446.CITY (2489) FAX 586.276.4077

cityhall@sterling-heights.net | www.sterling-heights.net

facebook.com/cityofsterlingheights | twitter.com/sterlingheights

**City Council**

<i>Mayor</i>	Michael C. Taylor
<i>Mayor Pro Tem</i>	Liz Sierawski
<i>Councilwoman</i>	Deanna Koski
<i>Councilman</i>	Michael V. Radtke Jr.
<i>Councilwoman</i>	Maria G. Schmidt
<i>Councilman</i>	Henry Yanez
<i>Councilwoman</i>	Barbara A. Ziarko

**City Manager** Mark D. Vanderpool

August 15, 2019

Re: Erdmann Road Reconstruction, City Project No. 19-341

Dear Resident:

On April 15, 2019 City Council awarded a contract for the reconstruction of Erdmann Road between Clinton River Road and 150 feet south of Ardel Drive. Construction is tentatively set to begin with pavement cutting the week of August 26<sup>th</sup> (weather permitting). As part of this project, the contractor will be removing the existing asphalt pavement and soil below the existing pavement, installing six-inch diameter edge drain, and installing a new seven inch thick concrete pavement with a stone base. We anticipate the area disturbed may reach up to two feet from the edge of road. The disturbed area will be restored at the end of the project. Any damaged sprinkler systems will also be repaired prior to restoration. Additionally, all existing driveway approaches will be removed and replaced with new concrete in order to provide a smooth connection to the new road surface.

The construction will be completed in four phases (see the back side of this letter for phasing diagram and paving limits). Residents within each phase will be given written notification via hand delivery a minimum of 24 hours prior to the start of concrete removal in each phase.

Homeowners adjacent to the replacement locations will not have access to their driveways during the time needed to complete that phase. Please take all precautions to have your automobiles parked outside of the phase limits when you are requested to do so. Construction for each phase will last approximately two weeks to allow for the pavement removal, replacement, and cure time. Do not drive on freshly poured concrete until the barrels are moved by the City, typically between five and seven days. This period is needed for the concrete to gain sufficient strength for vehicles and therefore provide for pavement longevity.

The contractor for this project is Galui Construction Co. The contractor may send out additional or more detailed notification about the construction schedule.

Postal service and trash pickup will be undisturbed. Your trash pickup will be on your normal day and will be picked up by the contractor. Place all trash in plastic bags and yard waste in paper bags. Please refrain from using trash cans.

Construction information and progress updates of the project can be located at [www.sterling-heights.net/conezone](http://www.sterling-heights.net/conezone). Thank you in advance for your cooperation. If you have any questions, please contact the Office of Engineering at (586) 446-2720. This road improvement project was made possible as a direct result of the voter-approved Safe Street Millage in November 2013.

Sincerely,

Andrew Konkle  
Civil Engineer II

cc: Jason Castor, City Development Director; Community Relations Director; Brent Bashaw, City Engineer; Fire Department; Police Department